16A MOUNT ARGUS ROAD
UMGENI PARK, DURBAN
TEL: 031 564 9820
CELL: 084 864 4300
TIM@TIMBROOKSAIRCONDITIONING.CO.ZA
VAT NO: 4180 277 289

QUOTE

QUOTE NO. Q5641
20 MARCH 2026

IMMANUEL CHURCH AT SEATIDES
STEF@METRICEDGE.CO.ZA
SIMPHIWE@METRICEDGE.CO.ZA

Thank you for the opportunity to quote on the following work:

- Supply and install Alliance units as below:
  - Classroom #1 – 1x 24,000Btu midwall unit installed with up to 3m piping.
  - Classroom #2 – 1x 24,000Btu midwall unit installed with up to 3m piping.
  - Classroom #3 – 1x 24,000Btu midwall unit installed with up to 3m piping.
  - Youth room – 1x 48,000Btu under-ceiling unit installed with up to 6m piping.
  - Meeting room – 1x 60,000Btu under-ceiling unit installed with up to 3m piping.
  - Stage – 1x 18,000Btu midwall unit installed with up to 6m piping.
  - Auditorium – 4x 60,000Btu under-ceiling units installed with up to 8/9m piping
  - Mother's room – 1x 12000Btu midwall unit installed with up to 6m piping.
  - Foyer – 1x 48,000Btu under-ceiling unit installed with up to 6m piping.
  - Prayer – 1x 12,000Btu midwall unit installed with up to 6m piping.
- Exposed piping is to be finished with white PVC trunking.
- Each unit will require a suitable power supply.

OPTION #1 – ALLIANCE NON-INVERTER UNITS

Classroom 1	R20,860.00
Classroom 2	R20,860.00
Classroom 3	R20,860.00
Youth room	**R38,840.00**
Meeting room	R40,740.00
Stage	R17,960.00
Auditorium	**R177,160.00**
Mother's room	R15,220.00
Foyer	R38,840.00
Prayer room	R15,220.00
Sub-total	**R406,560.00**
VAT @ 15%	R60,984.00
Total	R467,544.00

OPTION #2 – ALLIANCE INVERTER UNITS

Classroom 1	R23,500.00
Classroom 2	R23,500.00
Classroom 3	R23,500.00
Youth room	**R47,760.00**
Meeting room	R48,960.00
Stage	R18,800.00
Auditorium	**R210,040.00**
Mother's room	R16,400.00
Foyer	R47,740.00
Prayer room	R16,400.00
Sub-total	**R476,600.00**
VAT @ 15%	R71,490.00
Total	R548,090.00

ANTI-CORROSION COATINGS

- We strongly recommend that prior to installation all condensers are stripped and treated with Tectyl anti-corrosion coatings.

Classroom 1	R640.00
Classroom 2	R640.00
Classroom 3	R640.00
Youth room	**R740.00**
Meeting room	R840.00
Stage	R640.00
Auditorium	**R3,360.00**
Mother's room	R640.00
Foyer	R740.00
Prayer room	R640.00
Sub-total	**R9,520.00**
VAT @ 15%	R1,428.00
Total	R10,948.00

EXTRACTION

- Supply and install extraction provision to kitchen, disabled WC and downstairs ladies' and men's toilets.
    - Kitchen and disabled WC – supply and install 1x wall mounted extractor fan in each. Finished with external weather louvre.
    - Downstairs toilets – supply and install 1x system comprising of weather louvre, inline fan, silencers, round ducting and disc valves.
- Each fan will require a suitable power supply.

Tectyl treatments	R28,200.00
VAT @ 15%	R4,230.00
Total	R32,430.00

Regards

Nick Bolam

CONDITIONS

- All prices are valid for 30 days from date of quotation, subject to current stock prices and special offers.
- All goods remain the property of Tim Brooks Airconditioning (TBA) until paid in full.
- Final commissioning and handing over of controls will only be completed upon payment in full.
- Standard installation includes coring of one hole through brick, additional cored holes and penetrations through concrete will incur additional charges.
- Labour rates exclude work completed over weekends, after hours and public holidays.
- Suitable power supplies are required for each installation.
- Suitable drain points are required for each indoor unit.
- TBA does not undertake building, electrical, plumbing, waterproofing, painting, or carpentry work.
- TBA does not guarantee the performance of any existing air-conditioning unit or ductwork.
- Payment terms are strictly COD – cash or EFT upon completion of works.
- Where goods are delivered to site, and are placed in a lockable, secure, location, the safekeeping falls under the client's responsibility and goods are to be covered under the client's insurance policies.

WARRANTY – NEW INSTALLATIONS

- 12 months guarantee with Tim Brooks Airconditioning.
- 5-year conditional limited parts warranty on all Alliance and Samsung air-conditioning units – subject to regular maintenance and servicing by TBA.
- **Please note that all Samsung and Alliance units must be registered to activate the full 5-year warranty.**
    - This can be done by visiting www.fourwaysaircon.co.za

- In the event of failure water may be discharged from the evaporator (indoor unit), therefore no items that could be damaged by water should be placed directly below the evaporator. It is the consumer's responsibility to minimise the occurrence of this hazard by ensuring that:
    - The temperature is never set below 20 degrees.
    - Filters are kept clean.
    - Condenser (outdoor unit) is kept clear of obstructions – i.e., plants, grass etc.
    - Drainpipes are kept free of obstructions – i.e., ants, geckos, dirt etc.
    - Regular maintenance is completed – at least once annually.

- Part replacement warrantees are only offered as per the individual suppliers' policies and subject to testing.

BANKING DETAILS

- Please use only the following banking details. These can be checked against those on our invoices. If there are any issues or discrepancies, please contact us 031 564 9820 to confirm before making payment

    - Account name – Tim Brooks Airconditioning Pty Ltd
    - Branch name – Standard Bank Durban North
    - Branch code – 04 28 26
    - Account number – 250 123 649