98 Lilian Ngoyi Road
Berea
4001

Quote 222633

COMPANY: DF Strang **Date: 06/02/2026**

ATTENTION: Simon Strang

JOB ADDRESS: Immanual Church

Job: Deck, Stairs and Cladding.

Dear Simon,

Thank you for allowing us this opportunity to quote on your decking requirements. With our excellent after sales service and professional attitude, we ensure a smooth and hassle-free experience.

1. Job Description: Decking:

- To install a new Balau 24.081sqm deck as per plans with two steps on the front.
- Decking to be imported **19/90mm Balau** laid with 5mm spacings between.
- All timber used is iDeck timber which is of a high quality and harvested from sustainable forest management plantations.
- All decking will be laid onto a H4 CCA treated pine, 228/50mm wide beams, and 152/50mm wide joists. Set onto vertical H4 CCA treated gum poles secured into concrete footing.
- I use wider beams and joist as this helps with the longevity of the structure below the deck. It also gives the deck boards a bigger footing the sit on. This helps reduce the deck boards breaking on the joins.
- I use the deepest possible joist as this elevates any deck bounce.
- All structure below the deck to be painted black, this will hide the structure in the shadows below the deck.
- Deck to receive a two-deck board facia hiding the deck structure and creating a neat and clean deck.
- Timber sanded and oiled with Woodoc deck dressing.

2. Job Description: Balau stairs:

- To build a 17 tread Balau stairs and as per plans.

- Treads – 2 x 140/30mm with 5mm space, secured onto 40/40mm side cleats.
- Tread planks to be centrally secured together by single board.
- Stringers to be 215/40mm.

3. Job Description: Balau Cladding:

- To clad walls with 19/90 Balau Deck Boards.
- 38/38mm CCA H4 treated pine structure to be secured to painted all.
- Structure to be painted as per wall.
- Decking to be imported **19/90mm Balau** laid with 5mm spacings between.
- Running vertically on wall.
- Timber sanded and oiled with Woodoc deck dressing.

Pricing:

1.A.	Deck	R 73 155.00
2.A.	Stairs:	R 30 500.00
3.A.	Northwest Elevation Cladding	R 28 080.00
3.B.	Southwest Elevation Cladding	R 21 060.00
TOTAL :		**R 152 795.00 excl VAT**
VAT :		**R 22 919.25**
GRANT TOTAL:		**R 175 714.25 incl VAT**

PLEASE NOTE:

- A 5-year workmanship guarantee applies to new structures.
- Big Decks will supply all materials, fixings and epoxies where needed.
- Quote does not include cost of plans, or engineering certificates if required.
- Quote is valid for 30 days from above date.
- A 50% deposit payment is required to confirm.

I hope you find the above to your satisfaction, I look forward to being of service.

Kind regards

Mathew Goetsch
082 442 0331

Conditions:

- **BD cannot be held responsible for any damage to flora or fauna as a result of construction or renovation of timber structures. However every reasonable precaution is taken to avoid damage.**
- **BD can't be held responsible for delays with external work due to rain or adverse weather conditions.**
- **BD is not liable for any damage to service supply lines if not informed or provided with a clear plan before construction commences.**
- **BD External 220Volt power supply and water tap supplied by customer. If power supply must be provided by BD, an additional R220 per working day will be invoiced for a portable generator.**
- **BD is not liable for damage to masonry structures if not suitably constructed for fitment or removal of decking supports and balustrade posts. However drilling and fitment of these items are carried out by skilled personnel with care, but can't be held accountable if substrate is sub-standard and damages occur.**
- **BD staff must be advised and briefed on safety requirements of site. All BD staff will comply and provide their own safety equipment.**
- **Free access to property as well as parking in secure area for at least one company vehicle must be provided and arranged by the customer.**
- **If security access is required then customer must advise security.**
- **The customer must allow or arrange permission to store timber on site for the duration of construction with adequate security while BD staffs are not onsite.**

- **BD are not responsible for any movable possessions, such as outdoor furniture, pot plants, umbrellas, and the likes thereof. The work area must be cleared of these before the arranged start date. If BD are requested to move these items, it is entirely at the customers own risk.**
- **All 'left-over' timber on completion of the contracted job remains the property of BD. BD will always order excess timber to cover for damaged or warped timber supplied from the supplier, this**
- **Workmanship is guaranteed for 5 – years. BD cannot take responsibility for timber quality on exterior structures. Minor surface cracks may appear after a period. This is due to the nature of timber drying out in our harsh environment. It is normally no major concern to Balau as it is a very strong, durable forest timber. Wood rot on a small percentage of timber can occur prior to construction. BD is not responsible for this natural occurrence of pith or timber fault that can be seen from the outside of any timber. (Note: no liability will be taken for any other timber used on any external structure if requested or chosen by customer for performance. BD's preferred standards are to use hard forest timber that can withstand harsh environment conditions)**
- **The customer must make arrangements for the relevant irrigation co. to move and relocate any underlying irrigation pipes and valves in the way.**