135 Lena Ahrens Road
Berea / Durban

Email : craigwardpower@gmail.com
Cell : 076 4949 128

QUOTATION 3412

05-Feb-26

ATTENTION : MIKE & SIMON

DF Strang Buildings

Unit 3B
Gleneagles Office Park
Mount Edgecombe
4300

Cell : 082 902 4538
Email : simon@stranggroup.co.za
Email : chestman@iafrica.com

DESCRIPTION	
Electrical installation to proposed additions and alterations, lot 6459 Tongaat, Seatides, 172 - 188 Genazano Road for client Immanuel Church Seatides.	
MATERIAL & LABOUR	
UPPER GROUND STOREY PLAN	
KITCHEN	
* 1 x Single plug point - fridge	875,00
* 1 x Single plug point - MW	875,00
* 1 x 40amp isolator point - industrial coffee machine	1 295,00
* 3 x Double plug points - above counter	2 685,00
* 1 x Three pin / two pin combo plug point	895,00
* 1 x Stove isolator point	1 295,00
* Connect / fit oven and hob	395,00
* 4 x Recessed light points	1 980,00
* 4 x 10 watt Legend round LED downlighter fittings	1 660,00
* 1 x Ceiling fan point - wiring / assemble and install	895,00
* 1 x Pels 1400mm three blade ceiling fan with remote	4 950,00
* 1 x Light switch point	695,00
FOYER	
* 1 x Double plug point	895,00
* 1 x Three pin / two pin combo plug point	895,00
* 6 x Recessed light points	2 970,00
* 6 x 10 watt Legend round LED downlighter fittings	2 490,00
* 1 x Light switch point	695,00
LOUNGE AREA ADJACENT TO FOYER	
* 3 x Double plug points	2 685,00
* 2 x Three pin / two pin combo plug point	1 790,00

* 8 x Recessed light points	3 960,00
* 8 x 10 watt Legend round LED downlighter fittings	3 320,00
* 2 x Ceiling fan points - wiring / assemble and install	1 790,00
* 2 x Pels 1400mm three blade ceiling fans with remotes	9 900,00
* 1 x Light switch point	695,00
MAIN AUDITORIUM	
* 4 x Double plug points - general use	3 580,00
* 2 x Three pin two pin combo plug points - general use	1 790,00
* 6 x Double plug points - sound & media station	5 370,00
* 8 x Double plug points - main stage	7 160,00
* 32 x Recessed light points - main double volume	22 240,00
* 32 x 35 watt Legend round LED downlighter fittings	22 880,00
* 12 x Recessed light points - main stage	5 940,00
* 12 x 10 watt Legend round LED downlighter fittings	4 980,00
* 1 x Main light switch point (two banks of 16)	795,00
* 1 x Two way switching point	495,00
STORAGE ROOM 1 & 2	
* 4 x Recessed light points - main stage	1 980,00
* 4 x 10 watt Legend round LED downlighter fittings	1 660,00
* 2 x Light switch points	1 390,00
PRAYER ROOM	
* 1 x Double plug point	895,00
* 1 x Three pin / two pin combo plug point	895,00
* 4 x Recessed light points	1 980,00
* 4 x 10 watt Legend round LED downlighter fittings	1 660,00
* 1 x Ceiling fan point - wiring / assemble and install	895,00
* 1 x Pels 1400mm three blade ceiling fan with remote	4 950,00
* 1 x Light switch point	695,00
MOTHERS ROOM	
* 1 x Double plug point	895,00
* 1 x Three pin / two pin combo plug point	895,00
* 4 x Recessed light points	1 980,00
* 4 x 10 watt Legend round LED downlighter fittings	1 660,00
* 1 x Ceiling fan point - wiring / assemble and install	895,00
* 1 x Pels 1400mm three blade ceiling fan with remote	4 950,00
* 1 x Light switch point	695,00
TOILET / SMALL PASSAGE	
* 3 x Recessed light points	1 485,00
* 3 x 10 watt Legend round LED downlighter fittings	1 245,00
* 1 x Light switch point	695,00
EXTERNAL STAIRCASE	
* 2 x Outside wall light points	1 390,00
* 2 x Hero Pioled black trim square LED bulkhead light fittings	1 250,00
* 1 x Photocell point	695,00

OPEN DECK ARRIVAL	
* 1 x Outside wall light point - ramp walkway	695,00
* 2 x Ground light points - feature either side of main door - wooden decking	1 390,00
* 3 x Ground light points - feature signage wall - wooden decking	2 085,00
* 6 x Ground light points - wooden deck steps / stairs x 3	4 170,00
* 1 x Outside wall light point - stairs	695,00
* 2 x Hero Pioled black trim square LED bulkhead light fittings	1 250,00
* 11 x Spazio round black 5 watt LED ground light fittings	8 745,00
AIRCONDITIONING MAIN AUDITORIUM - PROVISIONAL	
* 4 x 40amp single phase aircon isolator points - separate cable runs from DB incl "D" curve circuit breakers and positioned at external condenser units (cassette type AC ceiling mount)	15 800,00
* 4 x Single plug points - indoor cassette units	3 500,00
SOUND / AUDIO VISUAL - PROVISIONAL	
* Provide 32mm conduit links between main stage and sound / media control - sound	2 950,00
* Provide 32mm conduit links between main stage and sound / media control - audio visual	2 950,00
* Provide 32mm conduit links between main stage and sound / media control - network	2 950,00
* Provide 32mm conduit links to 6 x speaker points - positioned around main auditorium	3 570,00
* Provide 32mm conduit links from visual screen back to sound / media control	2 950,00
* 1 x Power point - main screen	875,00
GENERAL	
* 1 x 3x12 way flush DB with door - incl all relevant switchgear - to be positioned in kitchen behind door (note this DB makes size allowance for a future three phase upgrade should it be required	9 895,00
* 16mm x 2 core ecc cable run from meterbox position on ground floor to new DB position in kitchen - incl all necessary conduits / chasing and fixings	9 500,00
* 1 x Geyser isolator point - upper level kitchen / toilet	1 295,00
* CBI Range of electrical sockets and light switches (listed above)	6 500,00
<u>LOWER GROUND STOREY PLAN</u>	
YOUTH / MULTI PURPOSE ROOM	
* 3 x Double plug points	2 685,00
* 2 x Three pin / two pin plug points	1 790,00
* 1 x TV point incl single plug @ 1,8m high on wall - TV screen	950,00
* 10 x Recessed light points incl concrete slab boxes	5 950,00
* 10 x 10 watt Legend round LED downlighter fittings	4 150,00
* 2 x Ceiling fan points - wiring / assemble and install	1 790,00
* 2 x Pels 1400mm three blade ceiling fans with remotes	9 900,00
* 2 x Outside wall light points	1 390,00
* 2 x Hero Pioled black trim square LED bulkhead light fittings	1 250,00
* 1 x Light switch point	695,00

* 1 x Aircon isolator point - separate cable feed from new DB on upper incl "D" curve circuit breaker - power positioned at condenser unit (18000 BTU)	2 650,00
EXISTING AREAS LOWER GROUND LEVEL - PROVISIONAL	
* Inspect and test existing electrical points and wiring for water damage and make sure installation complies with electrical regulations (advise client on any repairs required and costs)	3 950,00
TRAVEL	6 950,00
TOTAL	**R 287 405,00**
THREE PHASE UPGRADE - PROVISIONAL	
* 16mm x 4 core plus ecc cable - meterbox to DB upper level	14 500,00
* Three phase meterbox - lower level	3 950,00
* Additional switchgear - note three phase DB size allowed for in above quotation	2 950,00
* Three phase upgrade approx cost - Durban Metro Electricity Department	25 000,00
TOTAL	**R 46 400,00**

NOTES

1. This quotation is a cost estimate based on information provided and subject to changes made by the QS and client.
2. This quotation includes all light fittings according to a proper lighting design with calculation of lux levels.
3. This quotation includes all plug sockets and light switches.
4. Airconditioning design to be determined by specialist contractor.
5. Sound / audio visual requirements and design to be determined by specialist contractor.
6. A three phase upgrade to the electrical system may be required.

Thank you for the opportunity to quote

BANKING DETAILS
LS WARD
ABSA BANK
DURBAN NORTH BRANCH CODE 632005
ACCOUNT NO : 9274671369