DF STRANG BUILDINGS
THE ART OF CONSTRUCTION
RESIDENTIAL | RENOVATION | COMMERCIAL | INDUSTRIAL

LOT 6459 TONGAAT, SEATIDES,

172-188 GENAZANO ROAD
ALTERATIONS AND ADDITIONS

IMMANUAL CHURCH

DATE: 11 FEBRUARY 2026
PROVISIONAL BILLS OF QUANTITIES

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	BILL NO. 01				
	PRELIMINARIES				
1	Establishment	Item	1	85 000,00	85 000,00
2	Site Preliminaries and office overheads + QS measure sched of quants	Mnths	6	85 000,00	510 000,00
3	Contract Works Insurances--Existing Building-- Excluded CLIENT TO DO	Item			
4	Public Liability Insurances By Builder	Item	1	3 500,00	3 500,00
5	Site Toilets	Mnths	6	1 000,00	6 000,00
	TOTAL PRELIMINARIES AND GENERAL				**604 500,00**

DF STRANG BUILDINGS
THE ART OF CONSTRUCTION
RESIDENTIAL | RENOVATION | COMMERCIAL | INDUSTRIAL

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	BILL NO. 1				
	ALTERATIONS				
	Breaking up and removing				
1	Break/demolish existing columns/piers and cart away	No	4	850,00	3 400,00
2	Break existing surface bed (100mm thick assumed)	m²	10,65	1 750,00	18 637,50
	Demolishing and carting away				
3	Planter wall	m	7	175,00	1 225,00
4	Demolish existing Staircase	m²	6	450,00	2 700,00
	Taking down and removing				
5	Demolish existing walls and cartaway	m²	21	180,00	3 780,00
6	Remove and reposition existing single timber door	No	1	650,00	650,00
7	Existing rwdp catch pit repositioned	No	1	1 250,00	1 250,00
	Bricking up and making good				
8	Brickup openings	m²	3	950,00	2 850,00
	Make good existing walls				
9	Making good existing walls including painting (skim and paint) - downstairs area only	m²	567	150,00	85 050,00
10	Allowance for making good existing staircase	m²	9	250,00	2 250,00
11	Allowance for new floor finishes to existing staircase (R 200/m2 PC for tiling)	m²	15	490,00	7 350,00
12	Provision for repairs to cracks across site	sum	1	15 000,00	15 000,00
	Expose existing foundations				
13	Existing foundation to be exposed and dimensions measured. including making good once work/measuring is finished	m³	2	550,00	1 100,00
	Drill and dowel new slab to existing				

14	Drill and dowel chemical anchors into existing suspended slab to Engineer's details	m	19	1 500,00	28 500,00
	TOTAL ALTERATIONS				**173 742,50**

DF STRANG BUILDINGS
THE ART OF CONSTRUCTION
RESIDENTIAL | RENOVATION | COMMERCIAL | INDUSTRIAL

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	BILL NO. 2				
	EARTHWORKS, ETC.				
	For preambles see "Model Preambles for Trades 2017"				
	EXCAVATION				
	Excavation in earth not exceeding 2m deep				
1	Excavate for ground beams and pads	m³	39	110,00	4 290,00
2	Reduce levels under surface beds	m³	21	100,00	2 100,00
	Excavate back from the vertical face of excavations to the extent required for the insertion and removal of formwork and afterwards return, fill in and ram.				
3	Excavate back from the face of ground beam excavations exceeding 500 mm and not exceeding 1,5 m deep and 300 mm between the structure and the sides to be excavated back.	m²	4	110,00	440,00
	Risk of collapse of excavations other than bulk:				
4	Sides of trench and hole excavations not exceeding 1,5m deep	m²	76	10,00	760,00
	CARTING AWAY.				
	Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):				
5	Off site to a dumping site to be found by the Contractor	m³	15	150,00	2 250,00
	EARTH FILLING, ETC.				
	Compaction of in situ surfaces:				
6	Rip and recompact ground surface, including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 90% modified AASHTO density and trim to required levels.	m²	105	50,00	5 250,00
	Filling with material from the excavations compacted to a density of at least 95% Mod. AASHTO maximum density:				
7	Backfilling to trenches, holes, etc.	m³	23	90,00	2 070,00
	Filling with approved material G5 quality supplied and carted onto site by Contractor, compacted to a density of at least 98% Mod. AASHTO maximum density:				

8	Under surface beds	m³	11	850,00	9 350,00
9	Under ground beams/footings and pads	m³	5	850,00	4 250,00
	KEEPING EXCAVATIONS FREE OF WATER				
	Keeping excavations free of water				
10	Allow for keeping excavations free of water by hand or machinery.	Item	1	2 000,00	2 000,00
	TESTS				
	Prescribed density tests on filling:				
11	Modified AASHTO Density test	Item	1	1 000,00	1 000,00
	SOIL POISONING				
	Soil insecticide:				
12	Under floors and foundations etc. including forming and poisoning shallow furrows against foundation walls etc, filling in furrows and ramming	m²	186	17,00	3 162,00
	TOTAL EARTHWORKS				**36 922,00**

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	BILL NO . 3				
	CONCRETE, FORMWORK AND REINFORCEMENT				
	For preambles see "Model Preambles for Trades 2017"				
	UNREINFORCED CONCRETE				
	15MPa/19mm concrete				
1	Surface blinding	m³	2	1 800,00	3 600,00
	REINFORCED CONCRETE CAST AGAINST EXCAVATED SURFACES				
	25Mpa/19mm concrete				
2	Ground beams	m³	9	2 050,00	18 450,00
3	Concrete pads	m³	2	2 050,00	4 100,00
	REINFORCED CONCRETE				
	30Mpa/19mm concrete				
4	Surface beds	m³	11	2 200,00	24 200,00
5	Columns, stiffener piers and infill to brick pier	m³	4,66	2 200,00	10 259,04
6	Beams	m³	7	2 200,00	15 400,00
7	Slabs and inverted beams	m³	23	2 200,00	50 600,00
	CONCRETE SUNDRIES				
	Test Cubes				
8	Making and testing set of three 150 x150 x 150mm concrete strength test cubes	No	12	165,00	1 980,00
	Finishing top surfaces of concrete smooth with a steel float				
9	to top of slabs	m²	93	20,00	1 860,00
	Finishing top surfaces of concrete smooth with a wood float				
10	Surface beds, stair landings and treads etc	m²	71	20,00	1 420,00

	ROUGH FORMWORK				
	Rough formwork to sides				
11	Ground beams	m²	24	250,00	6 000,00
12	Pads	m²	4	250,00	1 000,00
13	Formwork to columns and stiffener piers with total height not exceeding 3.5m	m²	53,94	350,00	18 879,00
14	to edges n.e 300mm high, propped up not exceeding 3.5m	m	49	130,00	6 370,00
	Rough formwork to sides and soffits				
15	To isolated beams	m²	68	450,00	30 600,00
	Rough formwork to soffits				
16	Slabs not exceeding 250mm thick propped up, exceeding 1.5m not exceeding 3.5m high from bearing level.	m²	93	250,00	23 250,00
	MOVEMENT JOINTS ETC				
	Movement joints with "Jointex" between vertical concrete and Construction Joints				
17	Isolation joint, 10mm jointex sealed with polysulphide sealant to manufacturer's specifiction	m	41	40,00	1 640,00
	Saw cut joints				
18	3 x 60mm Saw cut joints in top of concrete	m	14	30,00	420,00
	REINFORCEMENT (PROVISIONAL)				
	Mild steel reinforcement to structural concrete work				
19	Bars in various diameters (assumed various kg/m3 as per Engineer)	t	7	17 000,00	119 047,60
	Fabric reinforcement to surface beds only				
20	Type 254 fabric reinforcement in concrete surface beds, slabs, etc	m²	71	85,00	6 035,00
	TOTAL CONCRETE FORMWORK AND REINFORCEMENT				**345 110,64**

DF STRANG BUILDINGS
THE ART OF CONSTRUCTION
RESIDENTIAL | RENOVATION | COMMERCIAL | INDUSTRIAL

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	BILL NO. 4				
	MASONRY				
	For preambles see "Model Preambles for Trades 2017"				
	SUBSTRUCTURE				
	14 Mpa Clay Maxi bricks				
1	230mm walls	m²	22	630,00	13 860,00
	SUPERSTRUCTURE				
	7 Mpa Clay Maxi bricks				
2	115mm walls	m²	100	315,00	31 500,00
3	115mm in beam filling	m²	12	315,00	3 780,00
4	260mm walls (including areas where existing brickwork is raised)	m²	437	630,00	275 310,00
5	Feature signage wall (brick pier)	m²	21,6	630,00	13 608,00
6	Piers, 270 x 230mm wide, in common brickwork (above concrete rafter beam)	No	12	375,00	4 500,00
	Brickwork reinforcement				
7	75mm Wide reinforcement built in horizontally	m	336	4,00	1 344,00
8	150mm Wide reinforcement built in horizontally	m	1 375,8	6,00	8 254,80
	Prestressed fabricated lintels				
9	110 x 70mm Lintels in lengths not exceeding 3m	m	164	75,00	12 300,00
	Brickwork sundries				
10	Brixeal bituminous compound emulsion paint to walls	m²	458,6	35,00	16 051,00
	TOTAL MASONRY				**380 507,80**

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	BILL NO. 5				
	WATERPROOFING				
	For preambles see "Model Preambles for Trades 2017"				
	DAMP PROOFING OF WALLS AND FLOORS				
	Gundle® API Brikgrip® DPC 250um' damp proof course (SANS 952-12011):				
1	On walls, stepped up in cavities, under cills, etc.	m²	38	120,00	4 560,00
	'Gundle® API A.T USB Green' 375um membrane to SANS 952-1:2011 laid with minimum 150mm overlaps and sealed with 'Gunplas®' pressure sensitive tape:				
2	Under surface bed	m²	71	40,00	2 840,00
	TOTAL WATERPROOFING				**7 400,00**

DF STRANG BUILDINGS
THE ART OF CONSTRUCTION
RESIDENTIAL | RENOVATION | COMMERCIAL | INDUSTRIAL

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	BILL NO. 6				
	CARPENTRY AND JOINERY				
	For preambles see "Model Preambles for Trades 2017"				
	TIMBER DOORS ETC.				
	Internal doors to Architect's specification				
1	D04- Internal door - Flush Panel semi solid internal door and installation complete	No	1	1 180,00	1 180,00
2	D06-Internal door - Flush Panel semi solid internal door and installation completeupply (based on the PC rate) and installation complete	No	1	1 180,00	1 180,00
3	D07- Internal door - Flush Panel semi solid internal door and installation complete	No	1	1 180,00	1 180,00
4	D08- Internal door - Flush Panel semi solid internal door and installation complete	No	1	1 180,00	1 180,00
5	D09-Internal door - Flush Panel semi solid internal door and installation complete	No	1	1 180,00	1 180,00
6	D10- Internal door - Flush Panel semi solid internal door and installation complete	No	1	1 180,00	1 180,00
	External doors to Architect's specification				
7	D12- Solid external door and installation complete	No	1	4 000,00	4 000,00
	Frames				
8	Internal single door frame installed complete including priming of back of frames	No	6	1 414,30	8 485,80
9	External single door frame installed complete including priming of back of frames	No	1	2 200,00	2 200,00
	Skirtings				
10	Allowance for Skirtings (PC rate R 45/m ex vat). Supply and install complete	m	220	80,00	17 600,00
	TOTAL CARPENTRY AND JOINERY				**39 365,80**

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	BILL NO. 7				
	CEILINGS AND PARTITIONS				
	For preambles see "Model Preambles for Trades 2017"				
	SUSPENDED CEILINGS				
	9.5mm gypsum plasterboard ceiling inclusive of all substructure as required, fixed to underside of SA pine roof trusses to specialist details				
1	Internal ceilings	m²	143	305,00	43 615,00
2	Extra over ceiling for 1000 x 1000mm trap door	No	2	1 550,00	3 100,00
	RAKED CEILINGS				
	9.5mm gypsum plasterboard ceiling inclusive of all substructure as required, fixed to underside of SA pine roof trusses to specialist details				
3	Internal ceilings	m²	222,2	350,00	77 770,00
	EAVES CEILINGS				
	Nutec ceilings to eaves				
4	To eaves	m²	44,1	380,00	16 758,00
	CORNICES ETC				
	Shadowline cornices to Interior designers specification				
5	20mm Shadowline cornice	m	242	95,00	22 990,00
6	Wall angle to external eaves installation	m	72	55,00	3 960,00
	Insulation to ceilings				
7	Insulation to Architect specification	m²	383,46	105,00	40 263,30
	PARTITIONS ETC				
	DRYWALL PARTITIONS				
	Partitions consisting of 51mm studs with 12,5mm thick Gypsum plasterboard on both sides (fully skimmed with suitable product as required by the Architect), with vertical supports at minimum 600mm centres (or as per manufacturers recommendation) including 50mm mineral wool insulation for acoustic enhancement. The Contractor shall include all				

	abutments, accessories and any other configurations as required on site in the rate below				
8	Partitions 3000mm high with bottom and top tracks plugged	m	4	1 741,65	6 966,60
	TOTAL CEILINGS AND PARTITIONS				**215 422,90**

DF STRANG BUILDINGS
THE ART OF CONSTRUCTION
RESIDENTIAL | RENOVATION | COMMERCIAL | INDUSTRIAL

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	BILL NO 8				
	FLOOR COVERINGS				
	Berber point 650 - 50cmx50cm Carpet tiles				
1	To internal floors	m²	261	375,48	98 000,00
	TOTAL FLOOR COVERINGS				**98 000,00**

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	BILL NO. 9				
	PLASTERING				
	For preambles see "Model Preambles for Trades 2017"				
	SUPPLEMENTARY PREAMBLES				
	INTERNAL PLASTER				
	Cement plaster on brickwork				
1	On walls	m²	651,7	100,00	65 170,00
2	Narrow widths	m²	65,17	150,00	9 775,50
	EXTERNAL PLASTER				
	Cement plaster on brickwork				
3	On walls	m²	441,7	100,00	44 170,00
4	To existing facebrick walls	m²	309	100,00	30 900,00
5	Narrow widths	m²	44,17	150,00	6 625,50
	Extra over for Feature plaster finish				
6	Feature plaster	m²	7	250,00	1 750,00
	CONCRETE SURFACES				
	Cement plaster on concrete surfaces				
7	Beams	m²	68	150,00	10 200,00
8	Columns and stiffeners	m²	49	150,00	7 350,00
9	Soffits of slabs	m²	93	100,00	9 300,00
	SCREEDS				
	Screeds on concrete				
10	40mm Thick on floors	m²	441	130,00	57 330,00
11	Decorated/Self levelling screed	m²	87	580,00	50 460,00

	TOTAL PLASTERING				**293 031,00**

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	TILING				
	BILL NO. 10				
	For preambles see "Model Preambles for Trades 2017"				
	FLOOR TILING				
	PC Allowance for Tile @ R250/m2 and allow to take delivery thereof, storage, profit and mark-up and fixing with adhesive to screed (screed elsewhere) and flush pointed with tinted (waterproof) grout				
1	To internal floors	m²	73	560,00	40 880,00
	TOTAL TILING				**40 880,00**

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	BILL NO. 11				
	PLUMBING AND DRAINAGE				
	For preambles see "Model Preambles for Trades 2017"				
	Note: The Contractor shall price all first and second fix plumbing items with all necessary pipework considered in terms of reticulation between points internally, as well as the pipework required from the external perimeter of the house. All external plumbing priced separately and is elsewhere.				
	FIRST AND SECOND FIX PLUMBING INSTALLATION OF SANITARY FITTINGS INCLUDING RETICULATION AND WASTE PIPEWORK FOR ALL WORK REQUIRED UP TO EXTERNAL ENVELOPE				
	Wash Hand Basins (WHB)				
1	First and Second fix plumbing including all necessary pipework, hot and cold water supplies complete (Sanitary Fitting elsewhere)	No	1	4 150,00	4 150,00
	Toilets (WC)				
2	First and Second fix plumbing including all necessary pipework, hot and cold water supplies complete (Sanitary Fitting elsewhere)	No	1	4 350,00	4 350,00
	Sink				
3	First and Second fix plumbing including all necessary pipework, hot and cold water supplies complete (Sanitary Fitting elsewhere)	No	1	4 150,00	4 150,00
	Prep bowl				
4	First and Second fix plumbing including all necessary pipework, hot and cold water supplies complete (Sanitary Fitting elsewhere)	No	1	4 150,00	4 150,00
	Geysers				
5	First and Second fix plumbing including all necessary pipework, hot and cold water supplies complete (Sanitary Fitting elsewhere)	No	1	4 150,00	4 150,00
6	General plumbing allowance including connection to existing system	Item	1	30 500,00	30 500,00
	TOTAL PLUMBING AND DRAINAGE				**51 450,00**

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	BILL NO. 12				
	PAINTWORK				
	For preambles see "Model Preambles for Trades 2017"				
	FLOATED PLASTER SURFACES				
	Primed and painted with two coats Plascon Wall and All to be applied in strict accordance with manufacturers specifications, colour to be confirmed by Architect				
1	Internal walls	m²	651,7	80,00	52 136,00
2	Narrow widths	m²	65,17	150,00	9 775,50
	FLOATED PLASTERED CONCRETE SURFACES				
	Primed and painted with two coats Plascon Wall and All to be applied in strict accordance with manufacturers specifications, colour to be confirmed by Architect				
3	Beams	m²	68	80,00	5 440,00
4	Columns	m²	46	80,00	3 680,00
5	Soffits	m²	93	80,00	7 440,00
	Primed and painted with two coats Plascon Wall and All to be applied in strict accordance with manufacturers specifications, colour to be confirmed by Architect				
6	External walls	m²	757,7	80,00	60 616,00
7	Narrow widths	m²	44,17	80,00	3 533,60
	WOOD SURFACES				
	One coat oil wood primer, one coat universal undercoat and two coats super universal enamel paint on				
8	Doors	m²	34	120,00	4 080,00
9	Door frames, etc	m²	4	100,00	400,00
10	Timber skirting	m	220	25,00	5 500,00
	ON PLASTER BOARD				

	Primer, undercoat and two top coats Plascon Wall and All as per manufacturers specifications				
11	On ceilings and cornices externally	m²	365,2	80,00	29 216,00
12	To Nutec ceilings externally	m²	44,1	120,00	5 292,00
13	Partitions	m²	4	80,00	320,00
	TOTAL PAINTWORK				**187 429,10**

DF STRANG BUILDINGS
THE ART OF CONSTRUCTION
RESIDENTIAL | RENOVATION | COMMERCIAL | INDUSTRIAL

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	BILL NO. 13				
	SUBCONTRACT PACKAGES				
	ELECTRICAL INSTALLATION, LIGHT FITTINGS, PLUGS AND SWITCHES				
1a	Electrical installation	Item	1	287 405,00	287 405,00
1b	Three phase Upgrade - Optional	Item	1	46 400,00	46 400,00
	TIMBER STAIRCASE AND TIMBER DECK				
2	Timber staircase and Timber deck construction	Item	1	103 655,00	103 655,00
	ALUMINIUM WINDOWS AND DOORS/LOUVRES				
3	Aluminium windows and doors	Item	1	302 123,93	302 123,93
	ROOF SUPPLY AND INSTALLATION				
4	Roof Supply and Installation	Item	1	477 690,60	477 690,60
	METAL PALISADE/GATE				
5	GMS screen/Palisade and gate	Item	1	38 510,60	38 510,60
	BALUSTRADES				
6	Balustrades	Item	1	17 556,93	17 556,93
	RAINWATER GOODS				
7	Rainwater goods	Item	1	29 700,00	29 700,00
	TIMBER SCREEN				
8	Timber screen	Item	1	49 140,00	49 140,00
	TOTAL SUBCONTRACT PACKAGES				**1 352 182,06**

DF STRANG BUILDINGS
THE ART OF CONSTRUCTION
RESIDENTIAL | RENOVATION | COMMERCIAL | INDUSTRIAL

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	BILL NO. 14				
	PROVISIONAL SUMS				
	IRONMONGERY				
1	Provisional allowance for Ironmongery of R 15,000 ex vat	Item	1	15 000,00	15 000,00
	LANDSCAPING				
2	Provisional Allowance for Landscaping of R 25,000 ex Vat	Item	1	25 000,00	25 000,00
	SANWARE/BRASSWARE/GEYSERS/GAS GEYSER ETC.				
3	Provisional allowance for sanware/brass ware/geysers of R 30,000 ex Vat	Item	1	30 000,00	30 000,00
	MIRRORS AND BATHROOM ACCESSORIES				
4	Provisional allowance for Mirros and bathroom accessories of R 5,000 ex vat	Item	1	5 000,00	5 000,00
	SIGNAGE				
5	Provisional allowance for Signage of R 10,000 ex vat	Item	1	10 000,00	10 000,00
	SEWER				
6	Provisional allowance for Sewer of R 15 000 ex vat	Item	1	15 000,00	15 000,00
	FEATURE WALL SIGNAGE				
7	Provisional allowance for Timber screen (referenced as repurpose existing on drawing) of R 5 000 ex vat	Item	1	5 000,00	5 000,00
	STAGE				
8	Provisional allowance for Stage of R 40 000 ex vat	Item	1	40 000,00	40 000,00
	JOINERY FOR SOUND AND MEDIA				
9	Provisional allowance for Joinery for sound and media of R 35 000 ex vat	Item	1	30 000,00	30 000,00

	TOTAL PROVISIONAL SUMS				**175 000,00**

DF STRANG BUILDINGS
THE ART OF CONSTRUCTION
RESIDENTIAL | RENOVATION | COMMERCIAL | INDUSTRIAL

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	BUILDERS WORK SUMMARY				
1	ALTERATIONS				173 742,50
2	EARTHWORKS				36 922,00
3	CONCRETE FORMWORK AND REINFORCEMENT				345 110,64
4	MASONRY				380 507,80
5	WATERPROOF				7 400,00
6	CARPENTRY AND JOINERY				39 365,80
7	CEILINGS				215 422,90
8	FLOOR COVERINGS				98 000,00
9	PLASTERERING				293 031,00
10	TILING				40 880,00
11	PLUMBING				51 450,00
12	PAINTWORK				187 429,10
13	SUBCONTRACT PACKAGES				1 352 182,06
14	PROVISIONAL SUMS				175 000,00
	TOTAL BUILDERS WORK				**3 396 443,80**

DF STRANG BUILDINGS
THE ART OF CONSTRUCTION
RESIDENTIAL | RENOVATION | COMMERCIAL | INDUSTRIAL

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	EXTERNAL WORKS				
	BILL NO. 1				
	WALKWAYS				
	For preambles see "Model Preambles for Trades 2017"				
	WALKWAY PAVING				
	Site Clearance				
1	Clear and grub within road reserve	m²	12	15,00	180,00
	Excavations				
2	Excavate to reduce levels for layer works installation (elsewhere)	m³	4	100,00	400,00
	Compaction				
3	Rip and re-compact excavated surface to Minimum 93% of Mod. AASHTO density	m²	12	40,00	480,00
	Filling with approved material G5 quality supplied and carted onto site by Contractor, compacted to a density of at least 100% Mod. AASHTO maximum density:				
4	to walkway areas	m³	2	750,00	1 500,00
	Bedding to Engineer's details				
6	20mm sand	m³	1	700,00	700,00
	Concrete pavers				
7	laid to architects detail on river sand (elsewhere) - R 300/m2 ex vat PC	m²	12	530,00	6 360,00
	TOTAL WALKWAYS				**9 620,00**

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	BILL NO. 2				
	STORMWATER				
	For preambles see "Model Preambles for Trades 2008"				
	Earthworks				
1	Excavate for pipe trenches not exceeding 2m deep	m³	27,75	100,00	2 774,60
2	Backfilling to pipe trenches	m³	12,41	110,00	1 365,40
3	Selected granular filling in bedding under and filling around pipes	m³	6,57	100,00	657,14
	UPVC storm water pipes				
4	110mm UPVC pipes	m	46	192,62	8 860,52
	Extra over 110mm pipes for:				
5	Bends	No	3	139,08	417,24
6	Junctions	No	1	188,54	188,54
	Channels				
7	Concrete stormwater channel	m	17	750,00	12 750,00
	SUNDRIES				
	Connections				
8	Connect to existing services	Item	1	2 500,00	2 500,00
	Testing				
9	Testing of the whole system	Item	1	3 500,00	3 500,00
	TOTAL STORMWATER				**33 013,44**

DF STRANG BUILDINGS
THE ART OF CONSTRUCTION
RESIDENTIAL | RENOVATION | COMMERCIAL | INDUSTRIAL

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	EXTERNAL WORKS SUMMARY				
1	DRIVEWAYS AND WALKWAYS				9 620,00
2	STORMWATER				33 013,44
	TOTAL EXTERNAL WORKS				**42 633,44**
	GRAND SUMMARY				
1	PRELIMINARIES AND GENERAL				604 500,00
2	BUILDING				3 396 443,80
3	EXTERNAL WORKS				42 633,44
	TOTAL EX VAT				**4 043 577,24**
	Markup @ 7,5%				303 268,29
	TOTAL INCLUDING MARKUP				**4 346 845,53**
	VAT @ 15%				652 026,83
	TOTAL INCLUDING VAT				**4 998 872,36**